

Mechanical Services Response to Council RFI

Project: 24-28 Wattle Street, Marrickville NSW

Prepared by: Northbridge Mechanical Services Pty Ltd

Date: 30 April 2026

Attention: Planning Consultant

We refer to Council's request for further information dated 21 April 2026 regarding potential acoustic impacts from the proposed rooftop mechanical plant.

The proposed mechanical plant is limited to split-system air-conditioning condensers serving the residential apartments and a small rooftop exhaust fan serving the ground-floor commercial tenancy amenities. At this stage, no commercial kitchen exhaust equipment is proposed.

The selected condenser units are modern inverter-type systems with low-noise operation. Manufacturer data indicates a typical sound pressure level of approximately 47 dB(A) at 1 metre for each outdoor condenser unit under normal operating conditions. The rooftop exhaust fan is expected to operate at approximately 52 dB(A) at 1 metre.

The rooftop plant will be positioned generally toward the centre of the roof, set back from the roof perimeter where practicable. Based on distance attenuation from the rooftop to neighbouring properties, it is expected that the resulting noise levels at surrounding receivers will be acceptable and will not create unreasonable disturbance.

The following measures are proposed:

- Use of low-noise inverter condensers.
- Mounting of condensers on proprietary anti-vibration feet.
- Locating plant away from the eastern roof edge where possible.
- Installation of a lightweight visual plant screen around the main condenser grouping.

The mechanical services design will be further developed during construction documentation. Final equipment selections may vary, but equivalent low-noise equipment will be used.

On this basis, we consider the proposed rooftop mechanical plant capable of operating without adverse acoustic impact on neighbouring residential properties.

Daniel Kwan
Senior Mechanical Engineer
Northbridge Mechanical Services Pty Ltd