



11 July 2024

Young Men's Christian Association of Sydney
254-326 Springwood Road
Yarramundi NSW 2753
c/ Invoke Property Pty Ltd

Attention: Messrs. Alex Torville & Ben Clifton

Dear Alex and Ben,

RE: YMCA Yarramundi Pool Refurbishment and Amenities Block 2 Replacement Tender

We are please to provide you with our tender submission for the Pool Refurbishment and Amenties Block 2 Replacement works for the YMCA at their Yarramundi precinct.

In addition to this tender letter we have also provided the Section 2 tender schedules, scope and tender price, clarifications and exclusion schedule, FFE schedule, signage schedule, prime cost / provisional sum and cost option schedule. In addition we have also provided comments relating to the conditions of consent in the DA matrix schedule.

We have endeavoured to provide you with a fully compliant tender and where we have been unable to align we have provided full disclosure and rationale. Notwithstanding this, it is our intent should we be successful, to provide the Principal with a fully complete and functional pool and amenities building that meets their needs and is in line with the project requirements. To that end we note that some items, while not specifically referenced in the tender scope, were identified in other tender documents or would be required to ensure compliance with the relevant Australian Standards and National Construction Code. We have sought to include such items to minimise any cost or time impost on the Principal during the course of the works outside of the contract scope.

p: (02) 9437 0055

a: 151 Saunders Road Oakville NSW 2765

DesignBuild Project Services Pty Ltd

ABN: 72 615 066 736

Builders Licence No. 317471C

Nominated Architect: Eliza Patterson NSWARB #11016



On a personal level, as a long time resident of the Hawkesbury I am passionate about projects which assist our community and I would be delighted to be able to assist the YMCA should we be successful.

We hope our tender submission is thorough, complete and meets the Principal's expectations. As always if there are any questions or if we are able to assist please do not hesitate to contact the undersigned.

I look forward to hearing from you.

Yours faithfully

A handwritten signature in blue ink, appearing to be 'M. Odd', written in a cursive style.

Michael Odd
Director

p: (02) 9437 0055
a: 151 Saunders Road Oakville NSW 2765

DesignBuild Project Services Pty Ltd
ABN: 72 615 066 736
Builders Licence No. 317471C
Nominated Architect: Eliza Patterson NSWARB #11016



SECTION 2 TENDER SCHEDULES

TENDER FORM

Tenderer's Details

Company Name:	Designbuild Project Services Pty Ltd
ACN:	615 066 736
ABN:	72 615 066 736
Address:	151 Saunders Road OAKVILLE NSW 2765 / Unit 9, 4 Campbell Street ARTARMON NSW 2064
Contact Person:	Michael Odd
Mobile No.:	0400 451 538
Email:	michael.odd@designbuildps.com

OFFER

To: YMCA NSW

EXECUTED on the date set out below

The Tenderer

Designbuild Project Services Pty Ltd

(ABN) (ACN)

72 615 066 736

of Address of Tenderer

151 Saunders Road Oakville NSW 2765

On Date 11 July 2024



1. in accordance with the Conditions of Tendering offers to carry out the Services set out and described in the RFT in strict conformity with the requirements of the RFT for the Fee tendered by the Tenderer.
2. represents that:
 - (a) the Tenderer has examined carefully and has acquired actual knowledge of the contents of the RFT and the other information made available in writing by the Principal to the Tenderer for the purpose of tendering;
 - (b) the information supplied by it in the Tender Schedules and the documents attached to the Tender Schedules are accurate and correct;
 - (c) the Tenderer can and, if selected as the Consultant, will:
 - (i) comply with all insurance obligations set out in the Agreement; and
 - (ii) comply with all occupational health and safety obligations set out in the Agreement;
 - (d) the Tenderer has examined all information relevant to the risks, contingencies and other circumstances having an effect on its tender and which is obtainable by the making of reasonable enquiries including the material contained in the Tender Documents, the material made available for the information of the Tenderer, any technical advice made available the Principal and the terms and conditions of any Approval relevant to the Services;
 - (e) the Tenderer has:
 - (i) examined the Project site and its surroundings, conditions and characteristics;
 - (iii) satisfied itself as to the access to the site, physical restrictions, environmental, health and safety requirements and the requirements for permits, consents and approvals; and
 - (iv) made an appropriate allowance in its tender for any effect thereon;
 - (f) the Tenderer has based its tender on its own investigations, determinations and assessment of the risks involved in carrying out the Services and carried out any further investigations necessary to provide adequate information for the purpose of tendering;
 - (g) the Tenderer has examined all statutory and regulatory requirements relevant to the Services and satisfied itself of its capacity to execute the Services in accordance with the terms and conditions of the Agreement without breaching any such terms, conditions, requirements, orders, regulations, rules, directions and practices;
 - (h) the Tenderer has satisfied itself as to the correctness and sufficiency of its tender for the Services and that its price covers the cost of complying with all of its obligations under the Agreement;
 - (i) the Tenderer has examined the PPR and Scope of Services and satisfied itself of its capacity to execute the Services in accordance with these documents and that its lump sum Fee covers the cost of complying with all of its obligations under the PPR and Scope of Services.
3. agrees to abide by and hold firm all of the terms and prices in its offer for a period of ninety (90) calendar days from the expiration of the closing date for tenders and these terms and prices will remain binding upon the Tenderer and may be accepted at any time by the Principal before the expiration of that period. The agreement contained in this paragraph is made in consideration of the administrative time and expense to the Principal in evaluating the Tenderer's offer.

EXECUTED by

_Designbuild Project Services Pty Ltd_____

Company Name

_615 066 736_____

ACN



In accordance with s.127(1)(c) of the Corporations Act 2001.

Director

A handwritten signature in blue ink, appearing to be 'M. Odd', written over a horizontal line.

_Michael Odd_____

Full name

_151 Saunders Road Oakvile NSW 2765_____

Usual address



EXPERIENCE OF KEY PERSONNEL

Please nominate the Key Personnel you are proposing to be available to provide the Works, together with a summary of their skills, qualifications and experience.

Key Person	Skills, qualifications & experience directly related to the specified Works.
Michael Odd - Project Manager	Bachelor Of Building (Const.) University of Technology Sydney Ass. Dip. App. Sc. Building - Hornsby TAFE Michael has 30 years experience in the building and development industries and has worked for some of Australia's largest private and public development and construction businesses including Walker Corporation, Barclay Mowlem (Laing O'Rourke) and Payce. During his career Michael has been involved in a number and significant construction projects including numerous multistorey residential towers, the Harold Park Paceway facilities upgrade, redevelopment of Breakfast Point, redevelopment of Wentworth Point. In addition Michael was also seconded by Housing NSW to project and development manage a number of key social housing projects within the Sydney metropolitan area as well as the Central and Mid-North Coasts. Michael has been a director of Designbuild Project Services since 2006 and during this time has delivered numerous prestige residential houses. In addition Michael was responsible for a number of major projects including the design and construction of Our Lady of the Angels Catholic Church Rouse Hill (which won the Hills Shire Council Building Award), the design and construction of (20) residential apartments in Harris Park for retired priests on behalf of the Catholic Diocese of Parramatta, the design and construction of the seminary at Harris Park including amenities, commercial kitchen, classrooms and (20) accommodation rooms for the Catholic Diocese of Parramatta. More importantly Michael is collegial and actively
Daniel Gray - Site Manager	Qualified Carpenter graduated Brookvale TAFE in 1993 Daniel has been a long term employee of Designbuild since 2010. During this time Daniel has been responsible for the site management, construction, quality and programming of projects. Daniel has sound technical knowledge of all aspects of the building process. Daniel is well organised and personable and is able to form solid relationships with our clients as well as the varying subcontractors that work on his sites. Daniel has a keen eye for detail and is able to manage all aspects of the building process but most importantly is fastidious in ensure that sites are well maintained and site safety is paramount



MANAGEMENT SYSTEMS

Provide information to illustrate the current status of the organisations:

- Quality Management System;
- Environmental Management System; and
- OH&S Management System.

Provide a copy of third-party accreditation if in place.

INSURANCE & LICENCING

The Tenderer must attach to this schedule a copy of a certificate of currency from its insurance company, for each policy of insurance required under the Conditions of Contract.

- Contract Works
- Public Liability
- Workers Compensation

The Tenderer must attach to this schedule a copy of their Contractor's licence details.

Clarifications & Exclusions Schedule

Item No.	Description	Included / Excluded
	General	
1	Note that this tender makes no allowance for unresolved design matters, structural engineers' costs, PCA fees, geotechnical inspections, arborist or any other consultant inspection fees.	Note
2	No allowance for works outside of the boundary. This tender makes no allowance for works outside the pool fence line with regard to the pool refurbishment works or outside the amenities building 2 building line unless noted otherwise.	Note
3	Preparation of dilapidation reports.	NAATS
4	This tender has assumed a 13 week defect liability period from the date of practical completion	Note
5	Upon application for final completion and / or handover (whichever comes first) any surface imperfections including but not limited to scratches, chips, dents or the like will not be classified as a defect or a warranty claim.	Note
6	Unless noted specifically within the finishes schedule all metal materials shall be finished in standard Colorbond, Dulux powder or anodised colours	Note
8	This tender allows a 10% deposit payable on execution of the contract	Note
9	This tender has allowed for a maximum of 5% retention of the total contract sum with 50% of the retained amount to be released upon practical completion and the remaining 50% on expiry of the defect liability period.	
10	This tender assumes all excavation in virgin excavated natural material (VENM) in material other than rock. This tender makes no allowance for excavation or removal from the site of contaminated material. This tender assumes all excavated material is to remain on-site, no tipping has been allowed.	Note
11	This tender makes no allowance for geotechnical testing, site classification, determination of suitability of excavations or other geotechnical advice.	Note
12	This tender assumes that the start date would be (10) business days from the date of execution in lieu of the (5) noted in clause	Note
13	This tender assumes that schedule 4 of the minor works contract is not applicable and therefore to be deleted. This tender has made no allowance for design work	Note
	Design	
14	Allowance for design during construction other than landscape design to the pool.	NAATS
15	Works not noted on the plans at time of tender or specifically noted as included	NAATS

16	Preparation of shop drawings other than toilet and shower partitions	NAATS
17	Should there be a difference between engineering design and architectural design, the engineering design has been allowed	Note
18	Any further designs, reports or other such works that may be required to resolve alterations to the amenities building including but not limited to the change of roof fall, raising of the slab and therefore roof level, moving of the building to the west per addendum 01 have not been allowed.	NAATS
	Authorities	
19	Applications and associated costs for authorities or other statutory bodies including but not limited to Sydney Water, Water NSW, Hawkesbury City Council, any private certifier, Jemena, Rural Fire Service, NSW Fire and Rescue, NSW Roads and Maritime Service and NSW Land Registry Office	NAATS
20	Identification surveys, plans of management, easements, restrictions on title or the like	NAATS
21	Certification and registration (if required) of the swimming pool and associated works by a suitably qualified and authorised certifier either private or Council has not been allowed	NAATS
22	Any required statutory approvals for the new pool pump room and storage has not been allowed	NAATS
23	Any further statutory approvals that may be required to resolve alterations to the amenities building including but not limited to the change of roof fall, raising of the slab, changes to the height of windows and therefore roof level, moving of the building to the west per addendum 01 have not been allowed.	NAATS
	Swimming Pool Refurbishment	
24	This tender assumes that the swimming pool is structurally adequate. No structural repairs to the pool shell or bond beam have been allowed	Note
25	This tender has allowed repair of minor non-structural cracking in the pool shell no greater than 1mm in width. Cracks greater than 1mm in width, spalling concrete, reinforcement treatment or other such remedial works have not been allowed	Note
26	This tender has allowed for 600mm wide waterline tile to the perimeter of the pool from the underside of the concrete bond beam. Tiles have been allowed from the contractors standard range	Note
27	This tender has allowed for a coping paver to the surface of the bond beam per item (20) of the scope of work. There has been no allowance to treat the vertical surfaces of the bond beam	Note
28	This tender has allowed the installation of a 100mm thick plain concrete slab on top of the existing hardstand to a distance not more than 3m from the pool	Note

	coping. The tender has allowed to ramp the concrete to provide a flush finish at the pool step area to comply with AS1428.1	
29	This tender has allowed for black powdercoat aluminium pool fence with tubular balusters and rectangular top and bottom rails. Please refer to the Alternate Pricing Schedule for a blade baluster option	Note
30	In the absence of a sewerage system able to cope with the water volume this tender has assumed that the existing pool water can be pumped out and reticulated onto the adjacent landscape for soakaway or evaporation dispersion. This tender does not allow to pump, cart and dispose of waste water at a licenced facility. Please refer to the Alternate Pricing Schedule for an off site disposal option.	Note
31	While item (14) of the scope of work requires that the pump room be double the size of the existing this would impact upon circulation space to the pool. To that end this tender assumes a pump and storage room structure no greater than 6m x 3m to the outside face of the external walls	Note
32	This tender has allowed for the replacement of the existing pool cover with a manually operated cover similar to a Daisy 525 solar pool cover	S&F
33	This tender has allowed for a PELICAN POOL AND SPA HOIST, SINGLE ARM, 150KG SWL - stainless steel, mobile hoist with 360 degree manual rotation. Includes: ● lifting hanger bar, rechargeable battery & charger. ● standard protective cover & standard fixing kit. ● Floating sling 200kg SWL adult standard size ● Anchor kit	S&F
34	With regard to the epoxy refinishing of the pool shell the tender has allowed for: ● Empty pool and remove hydrostatic valve ● Chlorine wash surface ● Repair surface with sand cement render ● Epoxy fill cracks ● Sand surface where required ● Acid wash ● Detergent wash ● Paint pool in three coats of Luxapool epoxy paint from the standard colour range ● Wait 10-14 days for paint to cure ● Install new hydrostatic valve	S&F
35	This tender allows for the following pool equipment: ● 2 x Waterco S702 filters with glass media ● 2 x Reltech 1.5hp pools pumps ● 1 x Astral Rola Chem series 9 (100/20) automated feeding unit	S&F

	• Vapure 55amp automatic salt chlorinator • 200 litre chemical storage drum • 14 x 15 litre chlorine drums (to replenish the chlorine storage drum) • 60 litre chemical storage drum • Rebalancing chemicals such as salt, bicarbonate soda, calcium, stabiliser, chlorine and oxidiser. Automatic Chlorine Feeder System Requirement In accordance with council regulations, all commercial pools used by the public must have an automated metered disinfectant dosing system. This system serves as a backup to ensure chlorine levels remain within the required range. While the pool can still operate as a saltwater pool, the automatic chlorine feeder will activate under certain circumstances, such as extreme weather conditions (e.g., hot and rainy days) or high swimmer load, to maintain optimal chlorine levels. This ensures the pool remains safe and compliant under all conditions. Chlorine and pH Management System The Vapure 55amp Salt Chlorinator will produce chlorine using the salt in the water, dosing the pool daily. The RC9 Dosing unit will measure the chlorine and pH levels constantly and dose accordingly, ensuring the chlorine and pH levels can be sustained, particularly when there is a heavy bather load and/or during intense summer weather. Having the combination of both systems provides the pool with the flexibility to handle variables that can cause the chlorine and pH levels to go out of range. This comprehensive approach ensures that water quality is consistently maintained, safeguarding health and compliance with regulatory standards.	
36	The tender has allowed for the soft landscape works as a provisional sum allowance to be resolved upon approval of the final landscape design. Please refer to the Provisional Sum and Prime Cost Item Schedule. This tender assumes that landscape maintenance will be by the Principal from the date of practical completion	S&F Note
37	The tender has allowed for bench seats equal or similar to the Felton in-ground aluminium bench seat. A total of 4 seats at 4m long have been allowed	S&F
38	This tender has allowed for (3) picnic tables equal or similar to Felton aluminium standard size park setting	S&F
39	This tender has allowed the replacement of the existing shade sails with similar shade cloth made from HDPE fabric. While this has a high UV rating it does not achieve the 100% blockout specified in item (28) of the scope. To achieve 100%	Note



	blockout requires the use of UPVC which places significant tensile loading on the anchor posts which requires specific structural engineering design. To that end the specified requirement is unable to be compiled with.	
40	Item (32) of the scope of work requires the allowance of 1 years water quality maintenance. Without being specified we have allowed for the following: • 52 site visits • Water testing and application of chemicals as required • Pool cleaning and removal of debris • Cleaning of filter baskets • Backwashing and rinsing of filter media • Supply and installation of a Waterlink Spin touch water testing unit including training of YMCA staff on its use. THis is to allow the YMCA to meet its daily water testing requirements as set by NSW Health • Supply of (100) Waterlink Spin Touch 204 water testing disks • Supply of a water testing log book • Supply of pool scoop, broom and telescopic pole The following items are not included in the maintenance allowance: • Daily water testing and recording in the daily sample log per legislative requirements. Logs must be maintained for (6) months. • Consumables such as chlorine, buffer, acid, algacides and other chemical or additives • Emergency call outs, after hours or weekend site visits	S&F NAATS
	Amenities Block 2	
41	Design and Consultants Fee We note that in tender addendum 01 item (8) requires the re-establishment of the threshold levels of the 3 adjoining paths and allow establish the path directly north directly north including stars and tactile indicators per item (9). We note that the raising of he slab by a further 200mm renders these paths even more non-compliant. In order to meet the tender requirement for satisfying the requirements AS1428.1 and the NCC we have allowed to remove the (2) oaths to the north and reconstruct to comply including ramps, landings, tactile indicators and handrails.	Note
42	The tender has allowed a provisional sum for the removal of any asbestos detected under the existing slab following demolition.	Note
43	The tender has allowed for 20 lineal metres of piercing. Additional piercing over his allowance has not been allowed.	Note
44	The tender has allowed Kordon or similar termite treatment to slab edges and penetrations	S&F

	The tender has allowed for villaboard lining to all internal wall with the exception of the plant room which is moisture resistant plasterboard. The tender allows for moisture resistant plasterboard to all ceilings. The tender allows for 55mm cove cornice to wal and ceiling junctions	S&F
45	The tender has allowed for the following with regard to tiling, water proofing and linear drains • wall and floor tile supply as a prime cost rate. Please refer to the Provisional Sum and Prime Cost Item Schedule for details • secondary waterproofing over the tile screed as per NCC 2022 • Stainless steel 100mm wide strip drains with removable linear stainless steel grates	S&F
46	The tender allows for the following plumbing and drainage scope Preparation Stage • Attend site and prepare existing bathroom amenities building services for demolition • Disconnect river water service supply line from existing building • Temporarily cap river water service supply line • Disconnect freshwater service supply line from existing building • Temporarily cap freshwater service supply line • Disconnect gas service supply line from existing building • Temporarily cap gas service supply line • Disconnect sewer line from existing building • Temporarily cap sewer supply line New Works Stage • Internal drainage lines for new bathroom amenity block. • Complete Hawkesbury City Council required Internal Drainage Inspection • Complete WAE Internal Drainage • Water service lines rough in for hot and cold water. • Vents with roof penetration and flashing. • Installation of stormwater service lines from down pipes installed by others. • Installation of PC Items as included in Fixtures and Fittings Supply Items. • Connection of all PC items to new plumbing and drainage service lines. All drainage connections in PVC Commission Stage • Re-connection of existing river water supply lines to showers, hot water heater, laundry, and WCs in amenities building.	S&F S&F S&F

	• Re-connection of existing fresh water supply lines to basins only in amenities building. • Re-connection of existing gas supply lines to 2 CF HWUs. • Re-connection of existing sewer line to multiple drainage points. • Complete Hawkesbury City Council required External Drainage Inspection. • Completion of required stormwater inspection sign off. • Supply of certificate of Compliance for all works completed. This tender assumes that connection to the existing water supplies, gas, stormwater and sewerage system in line with the project documents is satisfactory and assumes that these systems are capable of accepting the new works. This tender has made no allowance to upgrade, alter or otherwise amend the water supply, gas, stormwater or sewerage systems from the connection points immediately adjacent the new works. This tender makes no allowance for active fire systems including fire extinguishers, sprinklers, hose reels or hydrants.	Note NAATS
47	The tender allows for the following electrical scope of work Subboard Relocation Works • Installation of new three phase sub board on external wall of kitchen • Relocate and extend 95mm² three phase sub mains from Koala cabins to new sub board (mounted on external wall of kitchen) • Relocate and extend 95mm² three phase sub main supply from main switch board to new sub board • Relocate and extend 16mm² three phase sub mains from outdoor stage to new sub board • Relocate and extend light and power circuit from storage shed to new sub board • Relocate and extend C-bus underground control wire • Installation of 2 new underground pits, joints to be installed in these pits • Trenching and backfilling General Power & Lighting 2x Bathrooms each with • 12 downlights • 3 ducted exhaust fans • 1 exit light • 1 spit fire emergency lights • 2 double power points	S&F S&F

	• 1 smoke alarm 2x Accessible Bathrooms each with • 2 downlights • 1 ducted exhaust fan • 1 double power point • 1 spit fire emergency light • 1 sensor Plant Room • 1 LED light • 1 double power point • 1 sub board with RCD circuit breakers and main switch • 1 emergency lighting test board • Installation of c-bus relay and contactors (existing c-bus relays to be used- to be removed before demolition of building) Laundry • 1 double power point • 2 downlights • 1 spitfire emergency light Perimeter eave lighting • 8 downlights Subboard to plant rom Exit lights	
48	The tender allows for the following scope of work relating to toilet and shower partitions and vanity bench: Supply and install the Duracube 3000 Series Floor Mounted Overhead Braced (FOB) System. This system includes: - 13mm Compact Laminate Panels - Square Powder Coated aluminum headrail (Black or Grey to match the hardware) - Stainless Steel Screw Fixings - Overall system finish height up to 2000mm AFFL 8 x Standard inward swinging door/s 600W x 1700H, 200mm AFFL (Durasafe (Colour TBA)) with: - Nibs 2000H (Durasafe (Colour TBA)), - Set of Viva (Satin Chrome) hardware per door (3x lift-off hinges, 1x coat hook & bumper, 1x vacant & engaged indicator)	S&F S&F S&F

	10 x Standard outward swinging door/s 600W x 1700H, 200mm AFFL (Durasafe (Colour TBA)) with: - Nibs 2000H (Durasafe (Colour TBA)), - Set of Viva (Satin Chrome) hardware per door (3x lift-off hinges, 1x coat hook & bumper, 1x vacant & engaged indicator) 2 x Ambulant Inward swinging door/s 715W x 1700H, 200mm AFFL AFFL (Durasafe (Colour TBA)) with: - Nibs 2000H (Durasafe (Colour TBA)), - Set of Viva (Satin Chrome) Ambulant hardware per door (3x Hinges, 1x coat hook & bumper, 1x vacant & engaged indicator) - 1 x standard D handle (129mm) 10 x Divisional panels 1800W x 1700H, 200mm AFFL - (Durasafe (Colour TBA)) 8 x Divisional panels 1800-2400W x 1800H, 200mm AFFL (Durasafe (Colour TBA)) ** Note Vertical H Joint Required** 10 x Shower Seats 900W x 250D, 450mm AFFL (Durasafe (Colour TBA)) with: - Splash Nib up to 1700H x 260W, mounted on 200mm (Satin Chrome) adjustable pedestals leg in (Durasafe (Colour TBA)) 20 x Routed Rebate Privacy Edge Door (Reduces Opening by about 15mm) 20 x Sets of (Satin Chrome) Bolt Through Hardware to Hinges and Bumpers. Vanity Bench Supply and install the Duracube Vanity Bench System (VB). This system includes: - 13mm Compact Laminate Tops and Drop Front as noted - Steel Angle Brackets - Standard Vanity finish height 800mm AFFL Note al finishes from the Duracube standard ranges	S&F S&F S&F S&F S&F S&F S&F
49	This tender has made allowances for PC items over and above those noted in the FFE Specification where those items have been covered elsewhere in the tender documentation. Please refer to the FFE Schedule for clarification	Note
	Preliminaries	
50	Contract works, public liability and workers compensation insurance	Included
51	Temporary fencing	Included
52	Site toilet	Included



53	Site labour	Included
54	Supervision	Included
55	Project management	Included
56	Office overheads	Included
57	Signage	Included
58	Final clean and rubbish removal	Included
59	Craneage and scaffold	Included
60	Site establishment, sedimentation and erosion control measures	Included
61	Certificates and warranties	Included
52	Note all variations are subject margin of 15%	Note

Legend

SO: Supply Only

S&F: Supply & Fit

Incl: Included

NA: Not Applicable

NAATS: No allowance at this stage

FFE Schedule

Item	Make	Model / Note
Bench seats	Felton Industries	4 off 4m long inground aluminium bench seat
Picnic tables	Felton Industries	3 off standard size park setting
Accessible Toilet suite	Fienza Stella Care adjustable link toilet suite including backrest	
Accessible bathroom wall hung basin	Fienza Stella Care Basin with shroud one tap hole including chrome pop up waste	
Accessible bathroom basin mixer	Fienza Stella Care basin mixer with extended lever	
Accessible bathroom rear wall grab rail	450mm grab rail	
Accessible bathroom side wall grab rail	40 deg grab rail 900 x 700	
Accessible bathroom shower rail with integrated shower head	Fienza Luciana inverted T shape shower rail	
Accessible bathroom shower seat	Fienza Luciana Care shower seat	
Accessible bathroom shower mixer	Fienza Stella Care wall mixer	
Accessible bathroom	AS1428.1 compliant wall mirror -	

mirror	Fienza pencil edge rectangular mirror 450x950mm	
Ambulant toilet suite	Fienza Stella Care adjustable link toilet suite	
Ambulant toilet grab rails	40 deg grab rail 900 x 700	
Bathroom basins	Fienza Stella fully inset basin	
Bathroom basin mixers	Fienza Eco basin mixer	
Bathroom basin wastes	Chrome pop-up wastes 32mm overflow	
Bathroom toilet suites	Fienza Stella Senior adjustable link toilet suite	
Bathroom shower mixers	Fienza Stella Care wall mixer	
Bathroom shower arm and rose	Fienza Stella fixed arm shower arm and head	
Bathroom, accessible and ambulant robe hooks	Fienza Stella robe hooks	
Amenities	Mini stop cocks	
Amenities	Mixer hose	
Laundry washing machine stops	Base anti vandal stops	
Laundry tub	Everhard 45L stainless steel laundry trough and cabinet	Note no bench has been allowed
Laundry trough mixer	Fienza Eco sink mixer	



Amenities hot water units	Thermann 28lt gas instantaneous hot water units	
Amenities hot water unit valves	HWU valve assembly	
Bathroom and accessible bathroom hand dryers	Seton automatic hand dryer1 per bathroom, 1 per accessible - 4 total	
Bathroom and accessible bathroom soap dispensers	Sabco manual dispensers 2 per bathroom, 1 per accessible - 6 total	
Bathroom and accessible bathroom soap dishes	Fienza Empire soap shelf 1 soap holder per shower - 10 in total	
Bathroom mirrors	Fienza pencil edge 600x900	
Bathroom, ambulant and accessible bathroom toilet roll dispensers	Toilet roll dispensers	By Principal

Signage Schedule

Item	Make	Model / Note
Accessible bathroom 1	Unisex accessible toilet plus shower LH	Braille ABS plastic
Accessible bathroom 2	Unisex accessible toilet plus shower RH	Braille ABS plastic
Male Bathroom	Male ambulant toilet	Braille ABS plastic
Female Bathroom	Female ambulant toilet	Braille ABS plastic
Male Bathroom	Male toilet plus shower	Braille ABS plastic
Female Bathroom	Female toilet plus shower	Braille ABS plastic
Laundry	Laundry	ABS plastic



Prime Cost Item / Provisional Sum / Cost Option Schedule

Costs and rates below include GST

Item	Rate / Amount	Note
Landscape construction	\$20,000	Provisional sum for supply and installation of soft landscape elements including turf, soils, edging, plants.
Asbestos removal under amenities slab	\$5,000	
Pavers to pool coping	\$26/piece	
Turf	\$12/m2	Supply only. Rate applies to quantities greater than 100m2. Excludes turf underlay
Pavement	\$370/m2	Supply and place plain concrete
Fence	\$116/m	1200mm high black powdercoat aluminium fence with tubular balusters and rectangular top and bottom rails
Garden Beds	\$85/m2	Rate includes timber edge to one side, garden soil, mulch and 2 plants of 100mm pot size or smaller
Blade Fence	\$13,420	Extra over cost for pool fence with rectangular blade style balusters
Sandstone Log Seating	\$3,320	Extra over cost for 500 x 500 x 1000mm excavator sawn B grade sandstone logs in lieu of bench seating to pool area
Pool Water Disposal	\$22,000	Extra over cost to pump out, cart and dispose of pool water to a licenced waste water facility
Floor and Wall Tiling	\$25/m2	Supply rate only



Nominated Subcontractors

The following Principal preferred or local subcontractors have been used in the preparation of this tender. It is our intention to engage these subcontractors should we be successful

Trade	Subcontractor
Plumbing and drainage	Thomas Contractors
Electrical	Eaton Electrical
Pool plant and equipment installation and maintenance	Poolside Solutions
Toilet and Shower Partitions	Duracube
Pool hoist	Paramobility
Shade Sails	Alfresco Shade



DA Matrix Comments

The following DA conditions have not been included within the contact sum for the reasons listed:

DA No.	Condition	Comment
1	Approved plans and supporting documentation	The tender addendum has sought to change the construction from the approved design including altering the roof fall, altering the finished RL's, altering windows. The tender invitation does not reflect the DA approval
4	Part 6 certificates	We have allowed to provide certificates associated with obtaining the occupation certificate only and where specifically noted as being included. Any works associated with or the obtaining of further certificates is excluded. Our tender assumes that the PCA will provide the OC and mandatory critical stage inspection checklists along with any templates.
5	Occupation Certificate	We have allowed to provide certificates associated with obtaining the occupation certificate only and where specifically noted as being included. Any works associated with or the obtaining of further certificates is excluded. Our tender assumes that the PCA will provide the OC and mandatory critical stage inspection checklists along with any templates. We have allowed to coordinate mandatory critical stage inspections with the PCA
6	Compliance with the National	Our tender is predicated on the tender

	Construction Code (NCC)	documents, including any approved documents, meet the requirements of the relevant revision of the NCC. Further design and or construction work to address any non-compliances have not been allowed and would be a variation to the contract
7	Archaeology	Our tender allowance extends to notification of the Principal or their representative only. Further requirements in the condition such as the notification of Council and any further archaeological works are excluded.
12	Access for persons with a disability	This condition relates to evidence being provided to the certifier prior to issue of the construction certificate. As the construction certificate has been issued it is assumed that this condition is not required and has therefore been excluded.
13	Erosion and sediment control plan	This condition relates to evidence being provided to the certifier prior to issue of the construction certificate. As the construction certificate has been issued it is assumed that this condition is not required and has therefore been excluded. Erosion control measures as per the plan provided have been allowed.
15	Structural engineer's design	This condition relates to evidence being provided to the certifier prior to issue of the construction certificate. As the construction certificate has been issued it is assumed that this condition is not required and has therefore been excluded. Our tender allows for construction in line with the structural design provided. Our tender excludes

		further structural design if required
17	Bushfire assessment report recommendation 01	This recommendation relates to ongoing maintenance of the surrounding area. We anticipate this would be undertaken by the Principal as part of their normal operations and has therefore been excluded
17	Bushfire assessment report recommendation 02	We presume this is meant to relate to item 03 in the report
17	Bushfire assessment report recommendation 03	We presume this is meant to relate to item 04 in the report
35	Earthworks - general requirements	Part (d) of this condition requires that an independent auditor is to be engaged to validate fill material. This tender does not allow for this item
38	On-site sewage management - approval to operate	The tender design has the new amenities being connected to the existing on-site sewerage system, to that end it is assumed that this condition is not applicable and has therefore not been allowed.
40	Annual fire safety statement	Our tender assumes that there is an existing annual fire safety statement in place for the facility. To that end our tender only allows for the provision of certificates and to facilitate any inspections to be undertaken by the certifier engaged by the Principal to prepare an updated or interim annual fire safety statement

Yarramundi New Amenities Estimate			
Item	Description	Unit	Total excl GST
1	Preliminaries		\$45,515.70
	Temporary fence hire	Item	
	Safety sign	Item	
	Shade cloth supply	Rolls	
	Shade cloth installation	hrs	
	Contract administrator	weeks	
	Project manager	Days	
	Labourer	hrs	
	Contract works insurance	Item	
	Site management and safety application	item	
	Small tools and hire	item	
	Head office overheads	weeks	
	Bins	No.	
	Temporary toilet	Item	
	Tree protection	Item	
	Final Clean	Item	
2	Design Consultant Fees		\$84,635.10
	Allow to finalise the levels of the concrete access path surrounding the amenities in compliance with AS1428.1	item	
	Demolition of existing paths and excavate for new path routes	item	
	Form, reinforce, supply and place concrete to new paths including landings as required	item	
	Supply and install galvanised metal handrail to both sides of new paths	m	
	Supply tactile indicators to landings & ramps	no.	
	Installation of tactile indicators including adhesives	hrs	
	Annual Fire Safety Statement (interim) management to satisfy DA condition 40	Item	
3	Demolition, Excavation & Fill		\$61,645.50
	Allow for temporary disconnection / isolation of river water, potable water, gas, sewer, stormwater and power	incl	
	Allow to remove and dispose of any GWS asbestos fill as a provisional sum. Supply tipping dockets to validate tonnage against the provisional sum	P. Sum	
	Demolition of existing building	item	
	Allow for new fill to depth of 600mm under new slab and footpath. Ensure compliance to DA condition 35	item	
	Sedimentation & erosion control fencing and bunds	item	

	Batter edges and supply and install decomposed granite to northern side	item	
4	Form, Concrete, Reo		\$52,143.75
	Per structural details	Item	
5	Pest Control		\$2,781.00
	Allow termite treatment - allowed Kordon or similar	item	
6	Timber Frame, Linings and Fix-out		\$73,478.66
	Supply timber for new framing	item	
	Labour to install framing	hrs	
	Mobile scaffold	item	
	Supply villaboard to internal tiled walls	sheets	
	Supply moisture resistant plasterboard to ceilings and plant room walls	Sheets	
	Supply 90mm cove cornice to wall and ceiling junctions	Lengths	
	Plasterers to install plasterboard, cornice, set & sand	hrs	
	Capenters to install villaboard, doors, hardware, signage, bathroom accessories	hrs	
	Consumables	Item	
7	Insulation		\$4,403.25
	Supply and install insulation	item	
8	Roof and Wall Cladding		\$46,350.00
	Allow for BAL 29 rating requirements	item	
9	Screed, Waterproofing, Tiling		\$62,124.06
	Floor tile supply and install to all floors except plant room. Tiled floor area approx. 113m2		
	Concrete to plant room floor		
	Linear drain		
	Full height wall tiling. Tiles wall area circa 255m2		
	Waterproofing including over screed to comply with NCC 2022	item	
	Screed	m2	
	Supply floor tiles	PC Rate	
	Lay floor tiles	m2	
	Supply wall tiles	PC Rate	
	Lay wall tiles	m2	
	Supply linear drains	item	
10	Hydraulic (water, sewer, gas)		\$110,660.63
	Per design and specification	item	
	Downpipes	item	

11	Electrical		\$40,619.98
	Allow for new submeter board, attached to new post circa 5 metres from amenities block	item	
	Allow for new power, lighting, emergency lights, smoke alarms, bollard and lights	item	
	New subboard in plant room	item	
	Exit lights	item	
12	Windows and Doors		\$27,589.84
	Allow for 4x sliding windows (2400 x 300) in lieu of (2400 x 600) located above showers. Raise RL of x4 to avoid foul with shower rose	item	
	Allow to satisfy BAL 29	incl	
	Allow for window and door furniture	incl	
	Allow for commercial grade door closers to 2x bathroom doors	No.	
	Aluminium meshed flyscreens to all windows and doors except plant room	No.	
	Glazed doors to be obscure glazing	No.	
	Supply BAL 29 rated doors and frames	No.	
	Door hardware	No.	
13	Shower / Toilet Partitions		\$51,506.44
	Allow for 2400 height shower and toilet partitions	No.	
	Allow to submit shop drawings to the superintendant for review / approval	incl	
14	Painting		\$17,381.25
	Allow painting to ceilings, eave soffits, doors and jambs	item	
15	Fixtures & Fittings Supply		\$31,069.56
	Accessible Bathroom		
	Toilet suite - Fienza Stella Care adjustable link toilet suite	No.	
	Back rest	incl	
	Basin - Fienza Stella Care Basin with shroud one tap hole	incl	
	Chrome pop-up waste	incl	
	Fienza Stella Care basin mixer with extended lever	incl	
	450mm grab rail	incl	
	40 deg grab rail 900 x 700	incl	
	Fienza Luciana inverted T shape shower rail	No.	
	Fienza Luciana Care shower seat	No.	
	Fienza Stella Care wall mixer	No.	
	AS1428.1 compliant wall mirror - Fienza pencil edge rectangular mirror 450x950mm	No.	

	Ambulant Toilet		
	Toilet suite - Fienza Stella Care adjustable link toilet suite	No.	
	40 deg grab rail 900 x 700	No.	
	Main Bathroom & Laundry		
	Basins - Fienza Stell fully inset basin	No.	
	Basin mixers - Fienza Eco basin mixer	No.	
	Basin wastes - Chrome pop-up wastes 32mm overflow	No.	
	Toilet suites - Fienza Stella Senior adjustable link toilet suite	No.	
	Shower mixers - Fienza Stella Care wall mixer	No.	
	Shower heads - Fienza Stella fixed arm shower arm and head	No.	
	Robe Hooks - Fienza Stella robe hooks	No.	
	Mini stop cocks	No.	
	Mixer hose	No.	
	Laundry machine stops - Base anti vandal stops	No.	
	Laundry tub - Everhard 45L stainless teel laundry trough and cabinet	No.	
	Laundry mixer - Eco sink mixer	No.	
	HWU - Thermann 28lt gas instantaneous hot water units	No.	
	HWU valve assembly	No.	
	Hand dryers - Seton automatic hand dryer1 per bathroom, 1 per accessible - 4 total	No.	
	Soap dispensers - Sabco manual dispensers 2 per bathroom, 1 per accessible - 6 total	No.	
	Soap holders - Fienza Empire soap shelf 1 soap holder per shower - 10 in total	No.	
	Mirrors - Fienza pencil edge 600x900	No.	
	Toilet roll dispensers	excl	
	Signage		
	Unisex accessible toilet plus shower LH	No.	
	Unisex accessible toilet plus shower RH	No.	
	Male ambulant toilet	No.	
	Female ambulant toilet	No.	
	Male toilet plus shower	No.	
	Female toilet plus shower	No.	
	Laundry	No.	
	Total		\$711,904.71

Yarramundi Pool Refurbishment Estimate

Item	Description	Unit	Total excl GST
1	Preliminaries		\$32,305.95
	Temporary fence hire	Item	
	Safety sign	Item	
	Shade cloth supply	Rolls	
	Shade cloth installation	hrs	
	Contract administrator	weeks	
	Project manager	Days	
	Labourer	hrs	
	Contract works insurance	Item	
	Site management and safety application	item	
	Small tools and hire	item	
	Head office overheads	weeks	
	Bins	No.	
2	Design Consultant Fees		\$3,244.50
	Landscape architect fees	item	
3	Empty & Clean		\$1,390.50
	Pump out pool water	item	
4	Resurface Pool		\$14,484.38
	Apply primer coat	Item	
	Allow new epoxy	Note	
	Apply sealant	Note	
5	Waterline Tile		\$17,613.00
	Supply and install waterline tile 600mm wide incl depth markers	item	
6	Pump System & lines		\$18,580.56
	Remove and dispose of existing pump systems	item	
	Supply and installation of new pump system		
7	Pump & Store Room		\$50,842.47
	Replace pump house with new structure, double the size of the new existing pump house, allow for 2 compartments for the pumop and 1 for storage		
	Demolition of existing pump house & tip	item	
	Supply and install new slabs	item	
	Electrical works	item	
	Termite treatment	item	
	Form, reinforce, supply and place concrete to new slab	m3	
	Supply timber for new framing	item	
	Supply insulation	Bags	
	Supply villaboard lining to walls & ceilings	Sheets	
	Labour to install framing, insulation and lining, hardware	hrs	
	Mobile scaffold	Item	
	Trestles and planks	Item	
	Supply door hardware	No	
	Supply Timber door jambs	Lengths	
	Supply timber doors	No.	

	Supply flashings for door openings	item	
	Paint to doors and frames	item	
	Metal roof cladding	m2	
	Metal wall cladding	m2	
8	Pool Cover		\$3,522.60
	Demolish and tip existing cover	hrs	
	Supply new retractable cover	item	
	Labour to assemble and install new cover	hrs	
9	Accessible Hoist		\$16,435.71
	Allow for new sling style accessible hoist in accordance with Spec D3.10		
	Accessible water entry/exit for swimming pools. Lifting capacity 150kg	item	
	Allow for anchor footing system enabling sling to be temporarily stored		
	Labour to install ferrules for anchor system	hrs	
	Chemset supply	item	
10	Coping		\$9,281.59
	Prepare coping surface via cleaning and bonding agent application	hrs	
	Bonding agent and roller supply	item	
	Supply pavers	PC rate	
	Lay pavers incl sand & cement	Item	
11	Paving		\$37,080.00
	Allow new concrete slab to pool perimeter including ramp to step end.		
	Assume 3m width	item	
12	Turf, Garden Bed & Planting		\$23,175.00
	Allow to renew grassed area with new turf	P. Sum	
	New garden bed with native planting from shrubs no greater than 1.2m at full maturity, full length south fence, 2 metre wide bed, outside of pool area	P. Sum	
	Excavate and remove existing turf	incl	
	Supply new turf underlay	P. Sum	
	Supply new turf - allow for kikuyu	P. Sum	
	Lay turf	P. Sum	
	Labour to prepare garden beds	P. Sum	
	Treated pine garden edging	P. Sum	
	Supply mulch	P. Sum	
	Supply plants	P. Sum	
	Install plants	P. Sum	
13	Seating		\$11,210.91
	Remove existing seating	hrs	
	Picnic tables	no.	
	Allow 1 strip continuous seating along eastern side of pool - seat supply	no.	
	Allow to excavate for footings	hrs	
	Supply concrete to seat footings	no.	
	Mix and install concrete and install seating	hrs	
14	Shade Sails		\$22,207.44
	Remove and dispose of existing shade sails	hrs	
	Supply and install new shade sails	item	
	Paint existing steel posts	item	
	Mobile scaffold	item	

15	Pool Fence & Gate		\$12,699.90
	Demolish & remove existing pool fence - labour	hrs	
	Demolish & remove existing pool fence - tipping	item	
	New pool fence, match existing alignment from powdercoaed aluminium blades	item	
	Replace gate same location	item	
16	Maintenance		\$15,746.25
	Allow 1 year pool quality maintenance	item	
	Subtotal		\$289,820.76

PROFESSIONAL INDEMNITY CERTIFICATE OF CURRENCY

This is to certify that the details outlined below are current as at 27 February 2024.

Named Insured:	DesignBuild Project Services Pty Ltd		
Principal Address:	Unit 9/2-8 Campbell Street Artarmon New South Wales 2064		
Professional Business	Architect and project management services.		
Policy Number:	P0054486PI2024AU0		
Type of Insurance:	Professional Indemnity		
Period of Insurance:	From: 28 February 2024 To 28 February 2025 (both days at 4pm. local time at the Principal Address)		
Policy Wording:	Engineers & Architects Professional Indemnity ARCHEAPI2023		
Limit of Indemnity:	AUD 5,000,000 any one Claim or loss and in the aggregate (exclusive of Defence Costs)		
Reinstatement of Aggregate Limit	2		
Optional Extensions:	Optional Extensions will only apply if specified as covered, up to the sub-limit specified (if applicable):		
	Fidelity	Not Covered	
	Novated Contracts	Not Covered	
	Principals Indemnity	Not Covered	
	Proportionate Liability	Not Covered	
	Waiver		
	Seepage and Pollution	Not Covered	
	Third Party Cyber Security	Not Covered	
	Mitigation Costs	Covered	AUD 500,000 in the aggregate

All Certificates of Currency are issued by Arch Underwriting at Lloyd's (Australia) Pty Ltd on the basis that any Policy referred to in a Certificate of Insurance can be legally cancelled at any time for non payment of premium.

Any inquiries on this issue must be directed to the **Named Insured** or their Broker.



Ashleigh Mansell
Arch Underwriting at Lloyd's (Australia) Pty Ltd
For and on behalf of Certain Underwriters at Lloyd's
Signed at Sydney
27 February 2024
